Ringhals <u>Two Instrumentation & Control Exchange</u> TWICE







Replacement of entire Main Control Room (MCR), I&C System (SS and SRS), new Simulator and enhanced race-way separation & segregation, Temporary Operations Provision (TOP), LES and a new Rod Control System and more.

VATTENFALL 🌅

Ringhals Two Instrumentation & Control Exchange TWICE





Ringhals Unit 2 (R2)

Type Pressurized Water Reactor (PWR)

Net power 866 MW_e

Commercial Operation 1975

Reactor:

Supplier Westinghouse

Thermal output $2,652 MW_{th}$

Generators:

Supplier Alstom Power AB

Generator Voltage 19.5 kV

Turbines:

Supplier Stal-Laval Turbine AB

No. of Turbines 2

Rotation Speed 3,000 rpm

Cooling water flow 2*17,5 m³/s (2*6,180 ft³/s)

TWICE Basics

- New Software based I&C systems replaces 23 older analogical systems
 - -Safety System (SS)

ABBs AC160

Cabinets Situated in four newly built separate Safety Relay Rooms

Safety Related System (SRS)

Ovation (Emerson)

Diversified Actuation System (DAS)

Alternate Control Panel (ACP)

Remote Shutdown Panel (RÖP)

- New Main Control Room (MCR)
 - Large Screen Displays, work stations and Mauell panels
- New Simulator
 - A full-scale 'replica' of the MCR used for training and testing
- Lifecycle Engineering System (LES)
 - Independent test and development system for the software used in TWICE
- Temporary Operational Provisions (TOP)
 - Temporary Control Room (TCR) for monitoring functions to guarantee personal and plant safety (Radiation, fuel pit, fire alarms, ventilation etc.) during implementation.


VATTENFALL 😂

TWICE Basics (cont.)

- New Rod Control System
 - -Supplied by Mitsubishi
- Enhanced Separation and Segregation (Raceways)
 - -Four trains (A,B,C & D) for I&C-signals and power
 - New Electrical Penetration Assemblies (EPA) into Containment
 - IEC 61226 ("Cat. A")
- Replacement of Field Mounted Equipment (FME)
 - Original FME replaced by Transmitters etc.
- Commissioning and Testing
 - Factory Acceptance Test (FAT)
 - –Site Acceptance Test 1 (SAT 1)
 - -SAT 2, Systems Test
 - Operational Acceptance Test (OAT)

QA





Decommissioned EQ

Scrapped and Recycled:

- 920 km (572 mi) Cable (~230 ton)
- 220 Cabinets and larger objects
- > 1 MCR

> 1,900 units of Field Mounted Equipment (FME) (transmitters, limit-switches, etc.)



Installation of New Equipment

- > 328 Cabinets
- > 600 Junction boxes
- > 8,500 m (9,300 yd) of Race-way
- > 40 km (25 miles) of Conduit
- > 520 km (~310 miles) of Cable
- > 21,500 Cable connections
- > 1,773 new Field Mounted Equipment (FME)
- > ~30,000 signals
- > 1 MCR



TWICE Documents

- ~100,000 Documents handled in total (All at least once, some several times)
 - ➤ 48,000 Drawings/Circuit Diagrams
 - >1,500 Manuals
 - ➤ 11,000 Obsolete Documents
 - >17,000 Misc. Documents
 - ➤ 12,000 Test Reports



TWICE Work By order

- > 9,100 Work Permits/Work Orders
- > 60,000 keys handed out (All keys has been returned)
- Only 8 Accidents/Incidents during implementation
- > 800 people accommodated in Floating Hotel (Bibby

Challange)

> 340 kg (750 lb) of Candy



Timeline Major Events

➤ 1995-1999 Pilot Studies and price quotations.

>1999-03-26 RAB signed contract with Westinghouse

>2001 WP1 (WDP) Installed

➤ Dec 2002 Contract Renegotiated (2 year Delay)


≥2005-2007 Contract Renegotiated (impl. 2009)

➤ 2007 Simulator Complete

► 24 May 2009- Final Installation and Testing (Outage)

>28 Sept 2010 OAT Approved (Length of outage: 289 Days)

And all along the way: Work, work and more work.



Lessons Learned: Planning

Planning:

- The time schedule was never ever realistic.
 - ➤ Always leave some time for the unforeseeable and unexpected.
 - ➤ During a project that spans over 10 years: new requirements will arise during the journey.
- The Need for Resources increased over time
 - ➤ Ringhals and Westinghouse resources needed in the project increased compared to what was expected in the beginning of the project.
- Co-ordination between several different time schedules and parties didn't work.
 - ➤ One Plant, one Schedule! Not only in theory but in reality as well!
- Having the same, committed and engaged, people throughout the whole project is an major advantage.
 - ➤ Both for 'Key-positions' and 'Crew'

Lessons Learned: Communication

Communication:

- Good Communication is vital
 - ➤ Communication between different areas of expertise/departments was sometimes 'non-existent': "No man is an Island!"
 - ➤ Working in different time zones is sometimes helpful for 'fast' communication.
 - Communication during SAT Trouble-shooting was poor and created a lot of unnecessary work for all parties.
 - ➤ During the outage the communication between the project and maintenance-departments was very good.



Lessons Learned: Misc.

Misc.

- The Simulator was a big help during FAT.
 - >A vast number of issues was eliminated.
- You can save a lot of time, effort and money:
 - ...by not making haste.
- Qualification/Classification of Equipment
 - ➤ National Government Reqs. may exceed the International reqs.
 - ➤ Having both IEC (6)1226 and ANSI/308/603 classification in an existing plant sometimes makes it harder to harmonize policies.
- Reality vs. Documentation
 - ➤ Reality and Documentation doesn't always match

Lessons Learned: Misc.(cont.)

Misc.

- Having several Large Projects implemented at the same time takes it's toll on the customers organization and resources.
 - >TWICE.
 - >RPS
 - ➤(NICE/GREAT)
- Daylight Saving time:
 - ➤ Dates for start and end of daylight saving times should be harmonized ©


TWICE - New MCR Layout




R2 – Main Control Room 1974




TWICE – New Reactor Panel




TWICE – New Turbine Panel



TWICE – New Electrical Panel



TWICE - I&C Platform Reactor





R2 – Reactor Panel 1974



R2 - Turbine Panel 1974



Decommissioning - MCR



Decommissioning - MCR



Decommissioning – Outside MCR



Decommissioning - Outside MCR













TWICE - Installation - Relay Room



TWICE – Installation – SRS Cabinets



TWICE – Installation – Relay Room




TWICE - Installation - SRS Relay room



TWICE - Installation - SRS Cabinet



The most important thing is... to help each other!



Co-operate,



And to communicate.



