


# Mitsubishi US-APWR



November 8, 2011  
Mitsubishi Heavy Industries, Ltd.

# CONTENTS



- 1. US-APWR Overview**
- 2. Project Licensing Schedule**



# 1. US-APWR Overview

# What is US-APWR



- **The basic design concept of the US-APWR is the same as that of the APWR (Tsuruga 3,4) whose design is complete and is under the safety review and licensing process in Japan.**
- **All new APWR technologies have been fully tested, and verified.**
- **The US-APWR, 1700MWe class, is based on the established APWR technology with**
  - ✓ the latest technologies to improve plant efficiency
  - ✓ minor modifications to meet U.S. utility requirements

# Main Characteristics of US-APWR




	APWR	US-APWR
Electric Output	1,538 MWe	1,700 MWe Class
Core Thermal Output	4,451 MWt	4,451 MWt
Core	12 ft Fuel 257Assem.	14 ft Fuel 257 Assem.
SG Heat Transfer Area per SG	70,000 ft <sup>2</sup>	91,500 ft <sup>2</sup>
Thermal Design Flow rate per loop	113,000 GPM	112,000 GPM
Turbine	54 inch blades	70 inch class blades
Containment Vessel	PCCV	PCCV
Safety Systems	Electrical 2 trains Mechanical 4 trains	Electrical 4 trains Mechanical 4 trains
	HHSI × 4 Advanced Accumulator x 4 Elimination of LHSI	HHSI × 4 Advanced Accumulator x 4 Elimination of LHSI
I&C	Full Digital	Full Digital

# Advanced Technologies




## Reactor



- ◆ 1,700 MWe class large capacity
- ◆ Neutron reflector


## Engineering Safety Features



- ◆ Simplified configuration with four mechanical sub-systems
- ◆ In-containment RWSP
- ◆ Advanced accumulator

## Steam Generator

- ◆ High performance separator
- ◆ Increased capacity with compact sizing




## I & C

- ◆ Digital control & protection systems
- ◆ Compact console



## Turbine

- ◆ 70 inch-length blades in LP turbine
- ◆ Fully integrated LP turbine rotor





## 2. Project Licensing and Construction Schedule

# Design Certification Review



## ■ DC Review Schedule


- ✓ *Dec. 31, 2007, DC Application Submittal*
- ✓ *Feb. 29, 2008, DCA Docketed*

### Safety review

- ✓ *June, 2009, Phase 1*
- ✓ *Jan., 2012, Phase 2*
- ✓ *May, 2012, Phase 3*
- ✓ *Oct., 2012, Phase 4*
- ✓ *Jan., 2013, Phase 5*
- ✓ *May, 2013, Phase 6 (final SER issue)*

### Rulemaking

- ✓ *Oct., 2013, Issue final rule*



NRC HP <http://www.nrc.gov/>



# COLA Review Schedule



## ■ Comanche Peak Unit 3 and 4

- ✓ *Sep. 19, 2008 COLA submittal*
- ✓ *Dec. 2, 2008, COLA Docketed*

### Safety review

- ✓ *Oct., 2009, Phase 1*
- ✓ *Mar., 2012, Phase 2*
- ✓ *July, 2012, Phase 3*
- ✓ *Dec., 2012, Phase 4*
- ✓ *Mar., 2013, Phase 5*
- ✓ *June, 2013, Phase 6 (final SER issue)*

### Rulemaking

- ✓ *Nov., 2013, Issuance of COL*

## ■ North Anna Unit 3

- ✓ *Jun. 28, 2010, Technology design change to US-APWR*

### Safety review

- ✓ *Mar., 2012, Phase A*
- ✓ *Dec., 2012, Phase B*
- ✓ *May, 2013, Phase C*
- ✓ *July, 2013, Phase D (final SER issue)*

### Rulemaking

- ✓ *Nov., 2013, Issuance of COL*



Thank You